

DEPARTMENT OF TRANSPORTATION

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30th Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

TTY 711

*Flex your power!
Be energy efficient!*

June 13, 2012

01-Men-101-R69.4/R78.9

01-262004

Project ID 0100000005

Addendum No. 1

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN MENDOCINO COUNTY IN AND NEAR WILLITS FROM 1.3 KM SOUTH OF HAEHL OVERHEAD TO 2.9 KM SOUTH OF REYNOLDS HIGHWAY.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Tuesday, July 10, 2012.

This addendum is being issued to revise the Project Plans, the Notice to Bidders and Special Provisions, the Bid book, and the Information Handout.

Project Plan Sheets 6, 106, 241, 242, 389, 408, 514, 516, 854, and 899 is are revised. Copies of the revised sheets are attached for substitution for the like-numbered sheets.

Project Plan Sheet 241A is added. A copy of the added sheet is attached for addition to the project plans.

In the Special Provisions, Section 2-1.065, "ACCESS TO THE PROJECT SITE," is added as follows:

"2-1.065 ACCESS TO THE PROJECT SITE

To access the project site, prospective bidders must contact District 1 Right of Way at (707) 445-6429 or (707) 445-6426 Monday through Friday during normal business hours. Advance notice of at least 24 hours is required to access the project site."

In the Special Provisions, Section 4, "BEGINNING OF WORK, TIME OF COMPLETION AND LIQUIDATED DAMAGES" the following paragraph is added after the first paragraph:

"The start of any work that impacts areas of U. S. Army Corps of Engineers jurisdiction will be concurrent with the start of the Wetland Riparian Mitigation activities."

In the Special Provisions, Section 5-1.14, "RELATIONS WITH THE CITY OF WILLITS," is revised as attached.

In the Special Provisions, Section 5-1.15, "RELATIONS WITH THE COUNTY OF MENDOCINO," is revised as attached.

01-Men-101-R69.4/R78.9
01-262004
Project ID 0100000005

In the Special Provisions, Section 10-1.01, "ORDER OF WORK," the third paragraph is revised as follows:

"The Regional Water Board, as specified in General Condition number 40 of the 401 permit (WDIW #1B10019WNME), has determined that the following two projects; The Willits Bypass (Phase 1) Contract # 01-262004 and the Wetland Riparian Mitigation Contract # 01-262024 shall have no more than 70 000 square meters of combined disturbed soil area (DSA) at any time. Any DSA at the Oil Well Hill Optional Borrow site shall be included in the 70 000 Square Meter DSA Maximum. Any request for exceptions to exceeding the 70 000 square meters must be submitted for review and approval to the Engineer ninety days prior to exceeding the DSA limit. Any request for exception shall include the locations, size of area, anticipated duration of exposure (e.g. DSA without BMPs), and a location specific rain event action plan (REAP). All disturbed soil areas and exceptions to the 70 000 square meter limit shall be adequately documented in the site specific SWPPP. Only after the Regional Water Board has reviewed and approved the exception shall the Contractor proceed."

In the Special Provisions, Section 10-1.02, "CONTRACTOR SUPPLIED BIOLOGIST," subsection "GENERAL" subsection "Summary", the first paragraph is revised as follows:

"This work includes providing a Contractor supplied biologist to monitor construction and other activities to protect regulated species that may be harmed during construction activities. The Contractor supplied biologist shall be onsite every day that work occurs anywhere on the project to monitor all construction activities and provide daily reports as required by the various Contract Permits."

In the Special Provisions, Section 10-1.02, "CONTRACTOR SUPPLIED BIOLOGIST," subsection "GENERAL" subsection "Submittals", the fourth paragraph is revised as follows:

"The Daily Observation and Inspection Record: Submit a Daily observation and inspection record every working day during all contract work. The record will summarize oversight activities and compliance inspections, observation of special-status species, survey results, and monitoring activities required by the PLACs."

In the Special Provisions, Section 10-1.02, "CONTRACTOR SUPPLIED BIOLOGIST," subsection "CONSTRUCTION" subsection "Monitoring Schedule", the first paragraph is revised as follows:

"Monitor according to PLAC requirements, during active contract work and the following schedule:"

In the Special Provisions, Section 10-1.45, "EARTHWORK," the eighth paragraph is deleted.

In the Special Provisions, Section 10-1.47, "PETROLEUM CONTAMINATED MATERIAL" subsection "GENERAL" subsection "Summary", the fourth paragraph is revised as follows:

Roadway Excavation (Type DC) and Structure Excavation (Type DH) is defined as petroleum impacted material (soil) that requires stockpiling, for analytical testing that will be performed by the Engineer. Roadway Excavation (Type DC) and Structure Excavation (Type DH) material will be encountered during roadway and structure excavation work at the Shuster's Transportation Trucking facility located on 750 East Valley Street, Willits CA 95490, APN# 007-032-04, Caltrans Parcel Number 11662-01. Roadway Excavation (Type DC) will be encountered in excavating for Drainage System 52."

Addendum No. 1
Page 3
June 13, 2012

01-Men-101-R69.4/R78.9
01-262004
Project ID 0100000005

In the Bid book, in the "Bid Item List," Item78 is revised as attached.

To Bid book holders:

Replace page 6 of the "Bid Item List" in the Bid book with the attached revised page 6 of the Bid Item List. The revised Bid Item List is to be used in the bid.

Attached is a copy of the portion of the Information Handout titled "Oil Well Hill Disposal Site". Replace the first seven pages of "Oil Well Hill Disposal Site" with the attached.

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the Notice to Bidders section of the Notice to Bidders and Special Provisions.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the Bid book.

Submit bids in the Bid book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

This addendum and attachments are available for the Contractors' download on the Web site:

http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/01/01-262004

If you are not a Bid book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



REBECCA D. HARNAGEL
Chief, Office of Plans, Specifications & Estimates
Office Engineer
Division of Engineering Services

Attachments

5-1.14 RELATIONS WITH THE CITY OF WILLITS

The project areas is located within the jurisdiction of the City of Willits. The Contractor shall be fully informed of the regulations and conditions that may govern the Contractor's operations in these areas and shall conduct the work accordingly.

Before beginning construction activities within the City limits the respective contractor and subcontractors will acquire an Encroachment Permit. The process to start the permit can be found at the following website location:

[http://thecityofwillits.com/files/Engineering%20Department/STANDARD%20-%20Encroachment%20Permit%20Package%20\(rev%2001-2012\).pdf](http://thecityofwillits.com/files/Engineering%20Department/STANDARD%20-%20Encroachment%20Permit%20Package%20(rev%2001-2012).pdf)

Full compensation for conforming to the terms and conditions of the received permits and fees shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

5-1.15 RELATIONS WITH THE COUNTY OF MENDOCINO

The project is located within the jurisdiction of the County of Mendocino. The Contractor shall be fully informed of the requirements of regulations, and conditions that may govern the Contractor's operations in these areas and shall conduct the work accordingly.

Before beginning construction activities within the County limits the respective contractor and subcontractors will acquire an Encroachment Permit. The process to start the permit can be found at the following website location:

http://www.co.mendocino.ca.us/planning/pdf/3-Transportation_Binder_Edited.pdf.

Full compensation for conforming to the terms and conditions of the received permits and fees shall be considered as included in the contract prices paid for the various items of work involved and no additional compensation will be allowed therefor.

BID ITEM LIST

01-262004

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
61	170101	DEVELOP WATER SUPPLY	LS	LUMP SUM	LUMP SUM	
62	190101	ROADWAY EXCAVATION	M3	719 000		
63	190110	LEAD COMPLIANCE PLAN	LS	LUMP SUM	LUMP SUM	
64	190113	ASBESTOS COMPLIANCE PLAN	LS	LUMP SUM	LUMP SUM	
65	190114	DUST CONTROL PLAN	LS	LUMP SUM	LUMP SUM	
66	022779	ROADWAY EXCAVATION (TYPE DC)	M3	310		
67 (F)	192003	STRUCTURE EXCAVATION (BRIDGE)	M3	4421		
68 (F)	192008	STRUCTURE EXCAVATION (TYPE A)	M3	392		
69 (F)	192020	STRUCTURE EXCAVATION (TYPE D)	M3	3600		
70 (F)	192021	STRUCTURE EXCAVATION (TYPE DH)	M3	214		
71 (F)	192037	STRUCTURE EXCAVATION (RETAINING WALL)	M3	3863		
72 (F)	193003	STRUCTURE BACKFILL (BRIDGE)	M3	7051		
73 (F)	193013	STRUCTURE BACKFILL (RETAINING WALL)	M3	5298		
74 (F)	193030	PERVIOUS BACKFILL MATERIAL	M3	19		
75 (F)	193031	PERVIOUS BACKFILL MATERIAL (RETAINING WALL)	M3	308		
76	194001	DITCH EXCAVATION	M3	570		
77	198007	IMPORTED MATERIAL (SHOULDER BACKING)	TONN	450		
78	198010	IMPORTED BORROW (CY)	M3	741 000		
79	200101	IMPORTED TOPSOIL	M3	210		
80	022780	BOULDER	EA	38		